TOP**SECRET*** 2007/03/07: CIA-RDP02T06408R001100010046-8



PHOTOGRAPHIC INTERPRETATION REPORT

TYURATAM MISSILE TEST CENTER LAUNCH COMPLEX D

COPY 118 16 PAGES

25X1

AUTOMATIC DOWNGRADING

TOP SECRET

DECLASS REVIEW by NIMA/DOD

Approved For Release 2007/03/07 : CIA-RDP02T06408R001100010046-8

25X1

Pade Denied

| RECORD COPY | | | COPY NO. | PUB. DATE | | LOCATION | | MASTER | | R_ | DATE RECEIVED | LOCATION | | |
|--------------------------------------|-----|------------|---------------|----------------------------|--------------------------------|------------------|-----|--------------------------------|-------|-------------------------|--|------------------|----------|-----|
| Approved For Ret | | | | ease 2 | asel 2007/03/07 : (| | | CIA-RDP02T06 STOCK LEVEL | | 3408R001100010046- 1 | -B MAX I MUM | 10 | | |
| CUT TO COPIES O | | | DATE 7-74 | CUT TO COPIES | | DATE | | COPIE | S DES | STROYE | ED | | | |
| CUT TO COPIES CUT TO COPIES | | | DATE | CUT TO COPIES MASTER | | DATE | | | | | | | | |
| | | | DATE | | | | | | | _ | | | * | |
| DATE | | | | | NUMB | IUMBER OF COPIES | | DATE | | | | NUMBER OF COPIES | | |
| мо. | DAY | YR. | RECEIVED OR | RECEIVED OR ISSUED | | REC'D ISS'D | | MO. | DAY | YR. | RECEIVED OR ISSUED | REC D | 188'0 | 8 4 |
| 4 | 16 | 68 | Dist. Unit#10 | 8-117 | 10 | | 10 | | | | | | | |
| 12 | 9 | 68 | archers | 108 | | / | 9 | | | | | | | |
| 5 | 14 | 23 | Hast # 109 | -112 | | 9 | 0 | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | ······································ | | | |
| | | | | | | | | 1 | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | _ | | | | | | | | | |
| | | ļ <u>-</u> | | | | | - " | | | | | | | |
| | | | | | | ļ | | | | | | | | |
| | | | | | | | | | | | | | | · |
| | | | ` | | | | | | | | | | | |
| TITI | LE | NPI | <u> </u> | | | | | | CLAS | s. | LOCATION | 5034 | , | 25 |
| K 1 | | 1 | | | Marc | h 3.968 | 3 | TS. | | | // | 1001 | | 25 |

| Approved For <u>Release 2007/03/04</u> : CIA-RDP02T06408R00110 0 010046-8 | |
|--|------|
| Approved For Release 2007 03/07: CIA-RDP02T06408R001100010046-8 | |
| PHOTOGRAPHIC INTERPRETATION REPORT | |
| TYURATAM MISSILE TEST CENTER | |
| LAUNCH COMPLEX D | |
| | |
| | 25X |
| | |
| | |
| NATIONAL PHOTOGRAPHIC INTERPRETATION CENTER | |
| | |
| TOP SECRET | 25X: |

Approved For Release 2007/03/07 : CIA-RDP02T06408R001100010046-8

25X1

Pade Denied

25X1 25X1

25X1 25X1

. 25X1

25X1

25X1

.

LAUNCH SITE D1

Launch Site D1 (Figures 2 and 3) was the first of 2 prototype IIIA launch sites to be constructed. This first-

SUMMARY/CONCLUSIONS

the first generation of deployed Soviet hard ICBM launch

sites. Launch Site D1, the first of the 2 sites constructed

at the complex, is associated with the SS-7 missile system;

Launch Site D2, the more recently constructed site, is

probably associated with the development of the SS-9 missile

system. An interferometer/range-rate device was added

to the complex during the construction of Launch Site D2,

and is associated with that site. This type of electronics

facility, however, was never incorporated into the configuration of any of the deployed Type IIIA launch sites.

During late 1965, or early 1966, Launch Site D2 was subjected to a large high-explosives detonation in what appears to have been a vulnerability test. Visible damage to the launch site as a result of this test was confined to

INTRODUCTION

Launch Complex D is located at the eastern edge of the Tyuratam Missile Test Center at 46-01N 64-00E, approximately 36 nm northeast of the main support base and 12 nm east of Launch Complex H (Figure 1). When first observed

early stage of construction, and consisted mainly of a rectangular excavation and survey lines for a new road being extended eastward from Complex C. No evidence of

Major elements of Launch Complex D include 2 Type

IIIA launch sites, (D1 and D2), an interferometer/range-rate device, a probable observation point, an instrumentation site, and a complex support facility. An explosives storage area is located just south of the complex main road, 3.3 nm west-southwest of the complex support facility. The complex is served by a black top, all-weather road.

the complex was in an

damage to several frame buildings.

this activity was apparent on


Launch Complex D is the prototype IIIA facility for

Approved For TOP SECRET:


:CIA-RDP02T06408R001100010046-8


generation Soviet hardened launch silo probably was begun at Tyuratam late in 1960, along with a nearly concurrent program of operational deployment at various ICBM complexes. Many of the construction techniques employed at these sites went undetected because of small-scale photography of poor interpretability. Early coverage of Site D1 provided only vague indications of the nature of the construction activity, but additional details may be surmised from larger scale coverage at the deployed complexes. As presently configured, the site consists of 3 hardened launch silos built in a common large rectangular excavation with

a large notch in one of its longer sides. The silos are spaced 200 feet apart, on a line having an orientation of 315 degrees. West of the line of silos, and constructed in the notch in the side of the original excavation, is an earth-mounded control bunker. This control bunker has personnel entrances on 3 of its 4 sides and a number of unidentified structures (probably ventilators, observation ports, or, perhaps, antennas) on its roof. Each of the 3 silo headworks is approximately square, and canted about from the line through the silos to a loading azimuth of The large rectangular doors covering the silos are opened by




TOP SECRET






Approved For Release 2007/03/0

TOP SECRET



TOP SECRET

25X1



25X1

25X1

25X1

25X1

25X1

25X1

25X1

FENCE CLOSED DITCH FEET DESCRIPTION DIMENSIONS (FT)




FIGURE 8. INSTRUMENTATION SITE, LAUNCH COMPLEX D, TYURATAM MISSILE TEST CENTER.

02T06408R001100010046-8 Approved For TOP SECRET

sliding on rails in the direction away from the loading apron. From photography of the deployed complexes, it is known that rectangular equipment bunkers were constructed between the launch silos in the original excavation. Passageways for the movement of personnel between the silos, the equipment bunkers, and the control bunker are constructed parallel to the long axis of the excavation along both sides of the line of silos. Good interpretable photography of Site D1 reveals a low permanent structure, of undetermined function, adjoining much of the forward edge and the sides of the silo door in the closed position. A row of lattice towers flanks each side of the line of silos, and a number of small unidentified structures are on the hardstand in the vicinity of the silos. Northwest of the silos, but within the loop road serving the site, are 2 earth-mounded tanks and an earth-mounded structure. West of the silos, and to the left rear of the control bunker, is a rectangular area surrounded by an earth-banked wall which has been called a possible spray pond, although it never has been observed to contain an appreciable amount of liquid. Two earth-mounded probable tanks are at the eastern corner of this area. A dual-basin sump is north-northwest of the silos, just outside the security fence, and an earth-mounded structure is adjacent to the loop road north of the silos. A line of 2 probable telemetry antennas and 4 antenna positions adjoins the loop road southwest of the control bunker. Just inside the entrance to the site, along the eastern fenceline is a missile-ready building.

LAUNCH SITE D2

Launch Site D2 (Figures 4 and 5), approximately 0.8 nm east of Site D1, is a second Type IIIA launch site first seen Although Site D2 bears a strong exresemblance to Site Dl, a number of items distinguish the $2\ \mathrm{sites}$. Construction timing at this newer site differed considerably from that at the earlier site. Site D2 was considered complete in almost 3 full years after it was first seen, but Site D1 was considered to be complete only 2 years after the initial observation. During the period in which Site D2 was under construction at Tyuratam, a pronounced break occurred in construction starts at the deployed complexes. Between no construction starts were

recorded in the Type IIIA deployment program, and several launch sites of both hard and soft configuration were abandoned in an early stage of construction. The reason for this disruption in the construction program never has been definitely established, but the possibility has been raised that it involved a changeover from SS-7 to SS-9 deployment. Upon completion of Site D2, the main difference between it and Site D1 was the inclusion of 2 arch-roofed missileready buildings within the launch site. Other variations included a drive-in earth-mounded structure constructed adjacent to the southeast end of the earth-mounded control bunker, and additional construction activity near the southern fenceline where long narrow structures were being emplaced in shallow excavations. In _____ it became apparent that the central silo had been entirely covered by a flat-topped earth mound. In period of 4 months without photographic coverage of Launch Complex D, revealed a large crater 800 feet south of the right silo. Several of the frame buildings near the site entrance apparently had sustained considerable damage from a high explosives detonation at the location of the crater. The arrangement of curved and linear revetments, and of the previously identified buried structures near the southern fenceline, in a pattern radial to the crater strongly suggest that the explosion was deliberately set off, perhaps to determine the effect upon nearby facilities, including the launch site. Other than the 2 earth-mounded onsite missile-ready buildings and the earth mound over the central silo, the external appearance of Site D2 differs only slightly from Site D1. The variation in construction times, however, indicates that there are other differences between the sites which are not obvious and never have been fully understood.

INTERFEROMETER/RANGE-RATE **DEVICE**

An L-shaped interferometer* (Figure 6) was added approximately $0.7\ nm$ south of Launch Site D2 during late 1963 and early 1964. This facility consists of a central

TOP SECRET

25X1

[&]quot;The term "interferometer" is used to cover both true interferometers and range-rate measuring devices, as the 2 kinds of facilities cannot be distinguished on

Approved For Release 2007 55 5057 CIA-RDP02T 06408R001100010046-8 25X1

25X1


2**5**X1

25X1

Approved For Release 2007/03/07: CIA-RDP02T06408R001100010046-8

FIGURE 9. COMPLEX SUPPORT FACILITY, LAUNCH COMPLEX D, TYURATAM MISSILE TEST CENTER.

TOP SECRET



: CIA-RDP02T06408R001100010046-8

Approved For Rales 2007/03/07

25X1

25X1 25X1

25X1

25X1

FIGURE 11. EXPLOSIVES STORAGE AREA, LAUNCH COMPLEX D, TYURATAM MISSILE TEST CENTER.

: CIA-RDP02T06408R001100010046-8 Approved For Bole as 2007/03/0

Approved For Release 2007/03/01: CIA-RDP02T06408R001100010046-8 **TOP SECRET** 25X1 25X1 ROAD/HARDSTAND
FENCE
STATE EXCAVATION
100 0 250
FEET
SCALE 13000
INITIAL PROPERTY BISPLACEMENT. $\textit{FIGURE 12.} \ \ \textit{LAYOUT OF EXPLOSIVES STORAGE AREA, LAUNCH COMPLEX D, TYURATAM MISSILE TEST CENTER.} \\$

pproved For Release 2007/03/07 : CIA-RDP02T06408R001100010046-8

TOP SECRET

25¥1

25X1

25×1

antenna position at, and an earth-mounded control building near, the apex of the L, and a buried terminal antenna position at each extremity of the L. A second earthmounded structure is adjacent to the earth-mounded control building. Drainage ditches parallel both sides of each leg of the device, indicating a need to channel water away from

25X1

25X1

25X1

the legs. A security building is at the entrance to the facility, and 2 other small $\underline{\text{buildings are near the fence}}$ corner just to the west. In open ditch connected the interferometer with Launch Site D2, indicating a direct link between the 2 facilities, but interferometers never have been identifed at deployed Type IIIA sites, including those built following the construction hiatus of mid 1962 and early 1963.

ANCILLARY FACILITIES

Two small ancillary facilities are associated with the launch sites. One is a probable observation point (Figure 7) situated atop a knoll 0.5 nm west of Launch Site D1. Just to the south of this probable observation point, and just south of the complex main road, is an instrumentation site.

CIA-RDP02T06408R001100010046-8

Approved For Release CRET

This fence-secured facility (Figure 8) contains a large instrumentation building with 2 unidentified antennas and 5other antenna positions on its roof. Forward of the building are 4 telemetry/tracking antennas, and just south of the

building is a group of 5 smaller buildings.

COMPLEX SUPPORT FACILITY

Administrative and logistical support for Launch Complex D is centralized at the complex support facility $2.4\ nm$ west-southwest of Launch Site D1. This facility (Figures 9 and 10) appears to contain all the housing, administrative, recreational, and vehicular maintenance facilities necessary to support the personnel assigned to the complex. At the north edge of the complex support facility, is a separately fenced compound containing 2 earth-mounded, concrete, arch-roofed buildings and a circular, earth-banked tank or basin which often is filled with liquid. First evidence of the buildings was visible in and they appeared to be complete 14 months later in

The function of this pair of buildings

never has been established.

EXPLOSIVES STORAGE AREA

One other facility associated with Launch Complex D is an explosives storage area (Figures 11 and 12) 3.3 nm west-southwest of the complex support facility. Constructed during the summer of 1965, it was used only once for the storage of the high explosives used in the blast which created the crater at Launch Site D2 sometime between

REFERENCES MAPS OR CHARTS AMS. DESPA, Series 2, Sheet NL 41A/4, 1st ed., 1964, scale 1:50,000 (TOP SECRET REQUIREMENT CIA. C-DI5-82,776 (Revised) NPIC PROJECT 11055AF/66

- 12 -

TOP SECRET

25X1

25X1 25X1 25X1

25X1

25X1

Approved For Release 2700P3/SECREPP02T06408R001100010046-8